

**RECEIVED**

**OCT 27 2016**


**CITY OF MONROE**

**Drainage Report  
Raspberry Hill  
PFN: M2016-**

**for**

**TK Development, Inc.  
712 Kirkland Cir, Unit A104  
Kirkland, WA 98033  
425.879.5707**

**SITE LOCATION:  
18516 134<sup>th</sup> St SE  
Monroe, WA 98272**



Prepared by:  
Joseph M. Smeby, P.E.

Job No: 16-0916  
Oct. 2016

## TABLE OF CONTENTS

| <u>ITEM</u>  | <u>PAGE</u> |
|--|-------------|
| TABLE OF CONTENTS .....                                  | 1           |
| LIST OF FIGURES.....                                     | 2           |
| 1. INTRODUCTION.....                                     | 3           |
| 2. DRAINAGE INFORMATION SUMMARY FORM .....               | 4           |
| 3. EXISTING SITE CHARACTERISTICS and ASSUMPTIONS.....    | 6           |
| 4. NARRATIVE OF DEVELOPED SITE CHARACTERISTICS .....     | 7           |
| <u>A. DOE Minimum Requirements</u> .....                 | 8           |
| 5. DESCRIPTION OF PROPOSED EROSION CONTROL BMP'S .....   | 8           |
| <u>A. Erosion Control Risk Assessment</u> .....          | 9           |
| <u>B. SWPPP Minimum Elements</u> .....                   | 10          |
| 6. OFFSITE DRAINAGE ANALYSIS - UPSTREAM .....            | 10          |
| 7. OFFSITE DRAINAGE ANALYSIS - DOWNSTREAM .....          | 10          |
| 8. DETENTION STORAGE CALCULATIONS .....                  | 12          |
| <u>A. SUMMARY OF DETENTION CALCULATION RESULTS</u> ..... | 13          |
| <u>B. SCS CURVE NUMBER CALCULATION</u> .....             | 13          |
| 9. WATER QUALITY DESIGN .....                            | 14          |
| 10. CONVEYANCE CALCULATIONS .....                        | 14          |
| 11. MAINTENANCE AND OPERATIONS MANUAL.....               | 14          |
| APPENDIX A - STORMWATER CALCULATION.....                 | A-1         |
| APPENDIX B – OPERATIONS AND MAINTENANCE MANUAL.....      | B-1         |
| APPENDIX C – GEOTECHNICAL REPORT .....                   | C-1         |

## LIST OF FIGURES

| <u>ITEM</u> |  | <u>PAGE</u> |
|-------------|--|-------------|
| FIGURE 1    | VICINITY MAP .....                           | 15          |
| FIGURE 2    | EXISTING DRAINAGE BASIN MAP .....            | 16          |
| FIGURE 3    | DEVELOPED DRAINAGE BASIN MAP .....           | 17          |
| FIGURE 4    | SNOHOMISH COUNTY SOILS MAP .....             | 19          |
| FIGURE 5    | UPSTREAM/DOWNSTREAM TRIBUTARY AREA MAP ..... | 20          |

## 1. INTRODUCTION

This document is intended to provide engineering information necessary to support the preliminary sub-division application to the City of Monroe for the 28 lot sub-division proposed on this site. The site covers approximately 4.9 acres, of which approximately 4.9 acres will be cleared as a result of this project. Improvements to the south side of 134<sup>th</sup> St SE along this projects frontage along with new roads and connection to a future extension in the southeast corner of the site are proposed to provide access to the future lots.

This project proposes to construct a new public road within the plat to serve the future lots. In addition, frontage improvements along the south side of 134<sup>th</sup> St SE including new pavement, curb, planter and sidewalk will be constructed along the north side of the plat. This project will require the construction of driveways for each future lot, stormwater facilities and other utilities. The existing on-site soils are Tokul gravely medial loam, so infiltration will not be viable for this project. The proposed detention system will provide combined detention in a vault and water quality will be provided in a Contech Filter System downstream of the detention vault.

## 2. DRAINAGE INFORMATION SUMMARY FORM

Project: **Raspberry Hill**  
 PFN: **M2016-**  
 Engineer: **Omega Engineering, Inc.**  
 2707 Wetmore Ave  
 Everett, WA 98201  
 Attention: Joseph Smeby, P.E.

Total site area: **4.9 acres**  
 Offsite area: **0.00 acres**  
 Disturbed area: **4.9 acres**

Applicant: **Tk Develpoment, Inc.**  
 712 Kirkland Cir, Unit A104  
 Kirkland, WA 98033

Number of lots/Bldg: **28**

| <b>Drainage Basin Information</b>    | <b>Basin</b>       |
|--------------------------------------|--------------------|
| On-site Developed Area               | 4.9 acres          |
| Off-site Improved Area               | 0.00 acres         |
| Types of storage proposed            | Detention Vault    |
| Approximate total storage volume     | 67,137 cf per calc |
| Soil Types                           | Type C             |
| <b>Basin Data</b>                    |                    |
| Pre-developed run-off rates: 2-year  | 0.18 cfs           |
| 50-year                              | 0.61 cfs           |
| Post-developed run-off rates: 2-year | 0.10 cfs           |
| 50-year                              | 0.28 cfs           |

### **3. EXISTING SITE CHARACTERISTICS and ASSUMPTIONS**

The site is located south of 134<sup>th</sup> St SE and east of the Trombly Hill Subdivision, and in Section 36, Township 28N, Range 6E, Willamette Meridian. See Figure 1 - Vicinity Map. The entire property consists of a multiple lots totaling 19.7 acres.

Land use around the site is single-family residential. This site currently contains some single-family buildings. Frontage improvements will be required along 134<sup>th</sup> St SE which will include 18' of pavement, curb, gutter, planter and sidewalk.

The existing site is rectangular in shape approximately 327-feet long running east-west and 650-feet running north-south. The grades on the site are moderate. The vegetation found on the existing property is a mixture of landscaping including grasses and shrubs and native vegetation.

Grades on the site generally run from northeast to southwest. The existing soils on this site are Tokul, gravelly medial loam, which is considered Till. A site visit was conducted in September 2016. The weather was clear and sunny with temperatures in the 60's. No surface water was observed on this site.

The soil hydrologic types for this site have been identified as Type C or Till from the Snohomish County Soil Survey Map, see figure 5. The soil type mapped for this site is Tokul gravelly medial loam.

#### 4. NARRATIVE OF DEVELOPED SITE CHARACTERISTICS

This development proposes to create 28 new lots. The detention system will be designed for all the on-site improvements and some of the frontage improvements since they fall within a single "threshold discharge area" and the system has been sized to meet the 2005 DOE stormwater flow control and water quality standards.

The storm drainage system for this project has been designed to collect, treat and detain all of the new landscaping and impervious areas on this site. The off-site new impervious areas within 134<sup>th</sup> St SE, to the maximum extent practical will be collected as well and conveyed to the vault and filter for treatment and flow control.

The detention and water quality system has been designed using the WWHM2012 software and meet the 2005 State and current City standards.

## 4A. DOE MINIMUM REQUIREMENTS

### MINIMUM REQUIREMENT #1: PREPARATION OF STORMWATER SITE PLANS

This project proposes to construct new impervious surfaces in excess of the minimum threshold so a final stormwater site plan has been prepared with the full engineering plans for this project.

### MINIMUM REQUIREMENT #2: CONSTRUCTION STORMWATER POLLUTION PREVENTION (SWPPP)

#### 1: Mark Clearing Limits

One of the first steps in the "Construction Sequence" included on the clearing and grading plan sheets is for a surveyor to stake the limits of clearing and to have construction or silt fencing placed along the limits prior to any other construction activity.

#### 2: Establish Construction Access

The SWPPP calls for the proposed construction entrance to be installed as the second step after the staking of clearing limits. A detail is provided on the plans.

#### 3: Control Flow Rates

This project will construct the detention/water quality vault as a first step. This will be used as a sediment pond during construction and the control structure will be in place to attenuate flows throughout construction.

#### 4: Install Sediment Controls

This site and SWPPP proposes to construct a construction entrance to collect and contain the sediment on this site. In addition, inlet filters will be installed in the existing catch basins adjacent to the site. Interceptor swales with check dams will be used on-site to capture runoff and direct it to the necessary sediment pond/vault. These features are intended to minimize the opportunity for sediment to leave the site via stormwater or on vehicles. The construction of these features is one of the first items required in the "Construction Sequence".

#### 5: Stabilize Soils

The "Construction Sequence" and "TESC Notes" call for the stabilization of soils that remain unworked for certain lengths of time based on the time of year. Stabilization techniques may include but not limited to mulching, plastic sheeting or hydroseeding, notes have been added to the plan regarding protection for the stock pile area if necessary.

#### 6: Protect Slopes

No runoff will be directed toward the existing steep slopes in tract 999, in addition, any stockpile area will be protected as noted above.

#### 7: Protect Drain Inlets

All existing & proposed catch basins and area drains will have inlet filters installed to protect the conveyance system.

#### 8: Stabilize Channels and Outlets

Straw bale check dams will be used in the ditch along the north side of 134<sup>th</sup> St SE. Also, interceptor swales with check dams. These features will protect the existing and proposed channels from erosion.

#### 9: Control Pollutants

No outside chemicals are expected to be necessary for the construction of this project. All vehicles working on and around the site would need to meet the State requirements for emissions.

#### 10: Control DeWatering

Dewatering runoff will be directed to the detention/water quality pond system. The contractor shall monitor the sediment pond to ensure no erosion or excessive sedimentation occurs in the disposal areas.

#### 11: Maintain BMPs

The construction supervisor will be responsible for maintaining all BMPs during construction and working with the City to relocate or add BMPs as necessary as site conditions change.

#### 12: Manage the Project

It will be the responsibility of the Contractor and Developer to manage this project and coordinate with the City Inspector and Engineer.

#### Inspection and Monitoring:

Site inspections shall be done by a person who is knowledgeable in the principles and practices of erosion and sediment control. The person must have skills to first assess the site conditions and construction activities that could impact the quality of stormwater, and second assess the effectiveness of erosion and sediment control measures used to control the quality of stormwater discharges.

Whenever inspection and/or monitoring reveals that the BMPs identified in the Construction SWPPP are inadequate, due to the actual discharge of or potential to discharge a significant amount of any pollutant, appropriate BMPs or design changes shall be implemented as soon as possible.

#### Maintaining an Updated Construction SWPPP:

The construction SWPPP shall be retained on-site or within reasonable access to the site.

The SWPPP shall be modified whenever there is a change in the design, construction, operation, or maintenance at the construction site that has, or could have, a significant effect on the discharge of pollutants to waters of the state.

The SWPPP shall be modified if, during inspections or investigations conducted by the owner/operator, or the applicable local or state regulatory authority, it is determined that the SWPPP is ineffective in eliminating or significantly minimizing pollutants in stormwater discharges from the site. The SWPPP shall be modified as necessary to include additional or modified BMPs designed to correct problems identified. Revisions to the SWPPP shall be completed within seven days following inspection.

### MINIMUM REQUIREMENT #3: SOURCE CONTROL OF POLLUTANTS

The improvements proposed on this site will create 28-lots and new public roads. Residential sub-divisions do not require additional source control BMPS, but basic water quality is proposed on this site.

### MINIMUM REQUIREMENT #4: PRESERVATION OF NATURAL DRAINAGE SYSTEMS AND OUTFALLS

The vault outfall will be connected to the existing conveyance system along the west side of this project within the Trombley Hill subdivision. An existing CB exists along the southwestern corner of this project within a 15' public stormwater easement. The treated and detained runoff from this project will be discharged into the downstream system at this point. This is the natural downstream location since that plat borders this project to the west.

### MINIMUM REQUIREMENT #5: ON-SITE STORMWATER MANAGEMENT

Runoff from the new public road and future lots will be collected by CBs and conveyed to a detention/water quality system for this project. Roof runoff from each future SFR will be directed to an individual perforated stubout connection before discharging into the conveyance system within the future road right-of-way. The landscaping will be graded to drain toward the lot yard drains to the maximum extent feasible.

### MINIMUM REQUIREMENT #6: RUNOFF TREATMENT

A Contech Storm Filter system is proposed for this project downstream of the vault. This design meets the basic water quality treatment requirement for residential projects.

### MINIMUM REQUIREMENT #7: FLOW CONTROL

The design and analysis for this project requires the construction of a vault system which was sized using the WWHM2012 software.

### MINIMUM REQUIREMENT #8: WETLAND PROTECTION

No on-site or off-site wetlands have been identified on or near this project.

### MINIMUM REQUIREMENT #9: BASIN/WATERSHED PLANNING

The scope of this project is too small to justify a Watershed Plan.

### MINIMUM REQUIREMENT #10: OPERATION AND MAINTENANCE

A complete O&M manual has been provided with the full drainage report.

## 5. DESCRIPTION OF PROPOSED EROSION CONTROL BMP'S

Clearing, grading, and temporary erosion and sediment control plans have been prepared for this project. However, since a construction site is dynamic it will be necessary to re-assess the erosion control BMP's during construction and install additional measures when and if necessary.

Proposed temporary measures for this project will include the following BMP's:

- Installation of stabilized rock construction entrance(s).
- Interceptor swales
- Rip-Rap check dams
- Straw mulch, hydroseed or other mulching and planting method to stabilized unworked areas.
- Silt Fencing
- Sediment vault

Permanent measures to reduce or eliminate erosion or water quality degradation will include the following BMP's: (Under Future Phase/Permit)

- Paving all traffic areas
- Drainage collection system, including catch basins and floatable material separators
- Permanent landscaping in pervious areas.
- Limiting cut and fill slopes to 2:1 maximum
- Routine maintenance and inspection of the grounds and response to developing problems.

These proposed erosion control BMP's have been engineered for anticipated conditions in compliance with DOE guidelines. With proper installation, maintenance and inspection the proposed BMP's should result in minimal impact to the surrounding environment. The City retains the authority by code to require additional measures should the existing measures prove insufficient.

## A. SITE GRADING/EROSION CONTROL RISK ASSESSMENT

**SLOPE:** Existing grades onsite slope down from northeast to southwest ranging from 2.0% to approximately 12.0%. The proposed internal road grades will be no greater than 12%.

**CRITICAL AREAS:** Steep Slopes (Tract 999).

**SOILS:** In the development area of the site soils are hydrologic group C, (from Web-Soil Survey).

**GROUND MOVEMENT POTENTIAL:** N/A

**SOURCES OF WATER FOR EROSION:** Rainfall will be the only significant source of onsite runoff.

**MEASURES PROPOSED TO PREVENT/MINIMIZE EROSION:**

**TEMPORARY MEASURES:** Mulch cover, rock construction entrance(s), diversion swales, silt fencing are all proposed to be used to prevent or minimize erosion and siltation during construction.

**PERMANENT MEASURES:** Future measures will include permanent vegetative cover in pervious areas, limiting permanent cut and fill slopes to 2:1 maximum unless protected with a rockery face, asphalt pavement to stabilize all vehicle traffic areas and a piped conveyance system to control the location of runoff release. Routine maintenance of the grounds and response to developing problems will be a function of the property owner.

**CONCLUSION:** Proposed erosion control BMP's in compliance with DOE guidelines have been engineered for anticipated conditions. Civil construction plans include a detailed ESC plan that provides details and notes for the proposed BMP's. With proper installation, maintenance and inspection, the proposed BMP's should result in minimal impact to the surrounding environment. Based on the above information the Erosion Risk for this site is Low to Moderate. Reports, studies and designs for this site include:

*SEPA Checklist, by Others*

*Preliminary Engineering Construction Plans, by Omega Engineering, Inc.*

## B. Minimum Elements

### 1: Mark Clearing Limits

One of the first steps in the "Construction Sequence" included on the clearing and grading plan sheets is for a surveyor to stake the limits of clearing and to have construction or silt fencing placed along the limits prior to any other construction activity.

### 2: Establish Construction Access

The SWPPP calls for the proposed construction entrance to be installed as the second step after the staking of clearing limits. A detail is provided on the plans.

### 3: Control Flow Rates

This project will construct the detention/water quality vault as a first step. This will be used as a sediment pond during construction and the control structure will be in place to attenuate flows throughout construction.

### 4: Install Sediment Controls

This site and SWPPP proposes to construct a construction entrance to collect and contain the sediment on this site. In addition, inlet filters will be installed in the existing catch basins adjacent to the site, and straw bale check dams will be installed in the ditch along the east side of 191<sup>st</sup> Ave SE. Interceptor swales with check dams will be used on-site to capture runoff and direct it to the necessary sediment pond/vault. These features are intended to minimize the opportunity for sediment to leave the site via stormwater or on vehicles. The construction of these features is one of the first items required in the 4:

#### Install Sediment Controls

This site and SWPPP proposes to construct a construction entrance to collect and contain the sediment on this site. In addition, inlet filters will be installed in the existing catch basins adjacent to the site. Interceptor swales with check dams will be used on-site to capture runoff and direct it to the necessary sediment pond/vault. These features are intended to minimize the opportunity for sediment to leave the site via stormwater or on vehicles. The construction of these features is one of the first items required in the "Construction Sequence".

### 5: Stabilize Soils

The "Construction Sequence" and "TESC Notes" call for the stabilization of soils that remain unworked for certain lengths of time based on the time of year. Stabilization techniques may include but not limited to mulching, plastic sheeting or hydroseeding, notes have been added to the plan regarding protection for the stock pile area if necessary.

### 6: Protect Slopes

No runoff will be directed toward the existing steep slopes in tract 999, in addition, any stockpile area will be protected as noted above.

### 7: Protect Drain Inlets

All existing & proposed catch basins and area drains will have inlet filters installed to protect the conveyance system.

### 8: Stabilize Channels and Outlets

Straw bale check dams will be used in the ditch along the north side of 134<sup>th</sup> St SE. Also, interceptor swales with check dams. These features will protect the existing and proposed channels from erosion.

9: Control Pollutants

No outside chemicals are expected to be necessary for the construction of this project. All vehicles working on and around the site would need to meet the State requirements for emissions.

10: Control DeWatering

Dewatering runoff will be directed to the detention/water quality pond system. The contractor shall monitor the sediment pond to ensure no erosion or excessive sedimentation occurs in the disposal areas.

11: Maintain BMPs

The construction supervisor will be responsible for maintaining all BMPs during construction and working with the City to relocate or add BMPs as necessary as site conditions change.

12: Manage the Project

It will be the responsibility of the Contractor and Developer to manage this project and coordinate with the City Inspector and Engineer.

Inspection and Monitoring:

Site inspections shall be done by a person who is knowledgeable in the principles and practices of erosion and sediment control. The person must have skills to first assess the site conditions and construction activities that could impact the quality of stormwater, and second assess the effectiveness of erosion and sediment control measures used to control the quality of stormwater discharges.

Whenever inspection and/or monitoring reveals that the BMPs identified in the Construction SWPPP are inadequate, due to the actual discharge of or potential to discharge a significant amount of any pollutant, appropriate BMPs or design changes shall be implemented as soon as possible.

Maintaining an Updated Construction SWPPP:

The construction SWPPP shall be retained on-site or within reasonable access to the site.

The SWPPP shall be modified whenever there is a change in the design, construction, operation, or maintenance at the construction site that has, or could have, a significant effect on the discharge of pollutants to waters of the state.

The SWPPP shall be modified if, during inspections or investigations conducted by the owner/operator, or the applicable local or state regulatory authority, it is determined that the SWPPP is ineffective in eliminating or significantly minimizing pollutants in stormwater discharges from the site. The SWPPP shall be modified as necessary to include additional or modified BMPs designed to correct problems identified. Revisions to the SWPPP shall be completed within seven days following inspection.

## **6. OFFSITE DRAINAGE ANALYSIS - UPSTREAM**

From field observation and review of the available topography, it appears that some small areas to the northeast of this project will drain onto the site along with the existing roadside ditch east of the project within the 134<sup>th</sup> St SE R/W. The minor areas to the northeast will be allowed to sheet flow onto the site and will be collected by the proposed conveyance system. Runoff from the existing drainage ditch east of this project will be collected and piped within the 134<sup>th</sup> St SE R/W to the downstream connection point.

## **7. OFFSITE DRAINAGE ANALYSIS - DOWNSTREAM**

The project is bordered to the south by an existing easement and road R/W (Rainier View Rd SE). This road system collects the runoff from the existing site. This conveyance system appears to drain to the southeast and into a drainage pond. However, the actual drainage path could not be confirmed in the field.

It was confirmed and observed in the field however, that that existing runoff from this project is collected by an engineered conveyance system that conveys the site runoff through easements and R/W to the ultimate outfall location to the south. However, the exact location could not be located or observed.

## 8. DETENTION STORAGE CALCULATIONS

Current City code requires this site be analyzed using the 2005 DOE manual and the WWHM2012 storm water software. Since this site proposes using a detention vault the software will be used to size the system.

The vault has been sized to accommodate the developed conditions for this project and will release the flows to the southwest into the system described in the downstream analysis.

Refer to appendix 'A' for the full output from the WWHM2012 software.

## 9. WATER QUALITY DESIGN

Water quality for this project will be provided in the form of a Contech Storm Filter system. The Contech design team will help to size the final system at the time of construction plan submittal.

## 10. CONVEYANCE CALCULATIONS

The majority of the pipes designed for this project will receive up to 5.48 cfs for peak flows from the 100-year storm event. These flows will be concentrated by the inlet to the vault which is designed as a 12" pipe with a slope of spread through multiple inlets to the vault for which the greatest pipe flow rate will be slightly less than 5.8 cfs. These pipes are designed as 12" pipes ( $S=2.6\%$ , min.) with a peak flowing full capacity of over 8.0 cfs and therefore contain more than adequate capacity to handle the expected flows.

The vault outfall is the conveyance system which will convey the greatest flows from the project. The 100-year flow rate was calculated at 0.33 cfs which can also be conveyed within a 12" pipe. An emergency overflow will be provided for the detention system to accommodate any excessive flows in case of vault failure as part of the construction design/plan set.

Therefore, all pipes designed for this project have more capacity than required based on the expected flow to each leg of the pipe system.

## 11. OPERATIONS AND MAINTENANCE MANUAL

The Property Owners and HOA will be responsible for maintaining the stormwater and landscaping facilities within this development. Included in this manual are checklists for each feature specific to this project. Copies should be made of the checklists as necessary during routine inspections and required maintenance. Specific problems can be recorded along with the appropriate action taken.

These checklists are a guide for inspections and maintenance. The frequency of the inspections/maintenance is identified in the left hand column with the following abbreviations:

A = Annual (March or April preferred)

M = Monthly

S = After Major Storms (Use 1-inch in 24 hours as a guideline)

Routine inspections and maintenance will improve the long-term performance of the stormwater facilities. If at any time you are unsure if a problem exists or how to address a specific problem contact a Professional Engineer.

Refer to Appendix B for a list of each facility to be maintained and the appropriate maintenance checklist. (To Be Provided with Full Drainage Report)




FIG. 1



**OMEGA**  
ENGINEERING, INC.

2707 WETMORE AVE.  
Everett, WA 98201  
(o)425.387.3820 (f) 425.259.1958

VICINITY MAP  
RASPBERRY HILL

| DATE     | JOB NO. | SCALE      | SHEET  |
|----------|---------|------------|--------|
| 10/24/16 | 16-0916 | 1" = 2000' | 1 OF 1 |




FIG. 2




**OMEGA  
ENGINEERING, INC.**

2707 WETMORE AVE.  
Everett, WA 98201  
(o)425.387.3820 (f) 425.259.1958

EXISTING BASIN MAP  
RASPBERRY HILL

| DATE     | JOB NO. | SCALE     | SHEET  |
|----------|---------|-----------|--------|
| 10/24/16 | 16-0916 | 1" = 100' | 1 OF 1 |



  
**FIG. 3**



**OMEGA**  
**ENGINEERING, INC.**  
 2707 WETMORE AVE.  
 Everett, WA 98201  
 (o)425.387.3820 (f) 425.259.1958

**DEVELOPED BASIN MAP**  
**RASPBERRY HILL**

| DATE     | JOB NO. | SCALE     | SHEET  |
|----------|---------|-----------|--------|
| 10/24/16 | 16-0916 | 1" = 100' | 1 OF 1 |

**APPENDIX A**  
**STORMWATER CALCULATIONS**

**WWHM2012**  
**PROJECT REPORT**

## *General Model Information*

Project Name: Vault  
Site Name: Raspberry Hill  
Site Address:  
City: Monroe  
Report Date: 10/19/2016  
Gage: Everett  
Data Start: 1948/10/01  
Data End: 2009/09/30  
Timestep: 15 Minute  
Precip Scale: 1.20  
Version Date: 2016/02/25  
Version: 4.2.12

## *POC Thresholds*

---

|                               |                          |
|-------------------------------|--------------------------|
| Low Flow Threshold for POC1:  | 50 Percent of the 2 Year |
| High Flow Threshold for POC1: | 50 Year                  |

---

*Landuse Basin Data*  
*Predeveloped Land Use*

|                     |      |
|---------------------|------|
| Basin 1             |      |
| Bypass:             | No   |
| GroundWater:        | No   |
| Pervious Land Use   | acre |
| C, Forest, Mod      | 4.9  |
| Pervious Total      | 4.9  |
| Impervious Land Use | acre |
| Impervious Total    | 0    |
| Basin Total         | 4.9  |

|                   |           |             |
|-------------------|-----------|-------------|
| Element Flows To: |           |             |
| Surface           | Interflow | Groundwater |

*Mitigated Land Use*

Basin 1

Bypass: No

GroundWater: No

Pervious Land Use      acre  
C, Lawn, Mod            2.46

Pervious Total            2.46

Impervious Land Use    acre  
ROADS MOD              0.76  
ROOF TOPS FLAT        1.68

Impervious Total        2.44

Basin Total                4.9

Element Flows To:

Surface                    Interflow  
Vault 1                    Vault 1

Groundwater

*Routing Elements*  
*Predeveloped Routing*

## Mitigated Routing

### Vault 1

Width: 69.0937290026184 ft.  
 Length: 138.187458005236 ft.  
 Depth: 8 ft.  
 Discharge Structure  
 Riser Height: 7 ft.  
 Riser Diameter: 18 in.  
 Notch Type: Rectangular  
 Notch Width: 0.012 ft.  
 Notch Height: 4.018 ft.  
 Orifice 1 Diameter: 1.4 in. Elevation: 0 ft.  
 Element Flows To:  
 Outlet 1                      Outlet 2



Vault Hydraulic Table

| Stage(feet) | Area(ac.) | Volume(ac-ft.) | Discharge(cfs) | Infilt(cfs) |
|-------------|-----------|----------------|----------------|-------------|
| 0.0000      | 0.219     | 0.000          | 0.000          | 0.000       |
| 0.0889      | 0.219     | 0.019          | 0.015          | 0.000       |
| 0.1778      | 0.219     | 0.039          | 0.022          | 0.000       |
| 0.2667      | 0.219     | 0.058          | 0.027          | 0.000       |
| 0.3556      | 0.219     | 0.077          | 0.031          | 0.000       |
| 0.4444      | 0.219     | 0.097          | 0.035          | 0.000       |
| 0.5333      | 0.219     | 0.116          | 0.038          | 0.000       |
| 0.6222      | 0.219     | 0.136          | 0.042          | 0.000       |
| 0.7111      | 0.219     | 0.155          | 0.044          | 0.000       |
| 0.8000      | 0.219     | 0.175          | 0.047          | 0.000       |
| 0.8889      | 0.219     | 0.194          | 0.050          | 0.000       |
| 0.9778      | 0.219     | 0.214          | 0.052          | 0.000       |
| 1.0667      | 0.219     | 0.233          | 0.054          | 0.000       |
| 1.1556      | 0.219     | 0.253          | 0.057          | 0.000       |
| 1.2444      | 0.219     | 0.272          | 0.059          | 0.000       |
| 1.3333      | 0.219     | 0.292          | 0.061          | 0.000       |
| 1.4222      | 0.219     | 0.311          | 0.063          | 0.000       |
| 1.5111      | 0.219     | 0.331          | 0.065          | 0.000       |
| 1.6000      | 0.219     | 0.350          | 0.067          | 0.000       |
| 1.6889      | 0.219     | 0.370          | 0.069          | 0.000       |
| 1.7778      | 0.219     | 0.389          | 0.070          | 0.000       |
| 1.8667      | 0.219     | 0.409          | 0.072          | 0.000       |
| 1.9556      | 0.219     | 0.428          | 0.074          | 0.000       |
| 2.0444      | 0.219     | 0.448          | 0.076          | 0.000       |
| 2.1333      | 0.219     | 0.467          | 0.077          | 0.000       |
| 2.2222      | 0.219     | 0.487          | 0.079          | 0.000       |
| 2.3111      | 0.219     | 0.506          | 0.080          | 0.000       |
| 2.4000      | 0.219     | 0.526          | 0.082          | 0.000       |
| 2.4889      | 0.219     | 0.545          | 0.083          | 0.000       |
| 2.5778      | 0.219     | 0.565          | 0.085          | 0.000       |
| 2.6667      | 0.219     | 0.584          | 0.086          | 0.000       |
| 2.7556      | 0.219     | 0.604          | 0.088          | 0.000       |
| 2.8444      | 0.219     | 0.623          | 0.089          | 0.000       |
| 2.9333      | 0.219     | 0.643          | 0.091          | 0.000       |
| 3.0222      | 0.219     | 0.662          | 0.092          | 0.000       |
| 3.1111      | 0.219     | 0.681          | 0.095          | 0.000       |
| 3.2000      | 0.219     | 0.701          | 0.098          | 0.000       |

|        |       |       |       |       |
|--------|-------|-------|-------|-------|
| 3.2889 | 0.219 | 0.720 | 0.102 | 0.000 |
| 3.3778 | 0.219 | 0.740 | 0.106 | 0.000 |
| 3.4667 | 0.219 | 0.759 | 0.110 | 0.000 |
| 3.5556 | 0.219 | 0.779 | 0.115 | 0.000 |
| 3.6444 | 0.219 | 0.798 | 0.119 | 0.000 |
| 3.7333 | 0.219 | 0.818 | 0.124 | 0.000 |
| 3.8222 | 0.219 | 0.837 | 0.128 | 0.000 |
| 3.9111 | 0.219 | 0.857 | 0.133 | 0.000 |
| 4.0000 | 0.219 | 0.876 | 0.138 | 0.000 |
| 4.0889 | 0.219 | 0.896 | 0.143 | 0.000 |
| 4.1778 | 0.219 | 0.915 | 0.149 | 0.000 |
| 4.2667 | 0.219 | 0.935 | 0.155 | 0.000 |
| 4.3556 | 0.219 | 0.954 | 0.161 | 0.000 |
| 4.4444 | 0.219 | 0.974 | 0.184 | 0.000 |
| 4.5333 | 0.219 | 0.993 | 0.192 | 0.000 |
| 4.6222 | 0.219 | 1.013 | 0.200 | 0.000 |
| 4.7111 | 0.219 | 1.032 | 0.208 | 0.000 |
| 4.8000 | 0.219 | 1.052 | 0.217 | 0.000 |
| 4.8889 | 0.219 | 1.071 | 0.225 | 0.000 |
| 4.9778 | 0.219 | 1.091 | 0.234 | 0.000 |
| 5.0667 | 0.219 | 1.110 | 0.243 | 0.000 |
| 5.1556 | 0.219 | 1.130 | 0.252 | 0.000 |
| 5.2444 | 0.219 | 1.149 | 0.261 | 0.000 |
| 5.3333 | 0.219 | 1.169 | 0.270 | 0.000 |
| 5.4222 | 0.219 | 1.188 | 0.280 | 0.000 |
| 5.5111 | 0.219 | 1.208 | 0.290 | 0.000 |
| 5.6000 | 0.219 | 1.227 | 0.299 | 0.000 |
| 5.6889 | 0.219 | 1.246 | 0.309 | 0.000 |
| 5.7778 | 0.219 | 1.266 | 0.319 | 0.000 |
| 5.8667 | 0.219 | 1.285 | 0.329 | 0.000 |
| 5.9556 | 0.219 | 1.305 | 0.340 | 0.000 |
| 6.0444 | 0.219 | 1.324 | 0.350 | 0.000 |
| 6.1333 | 0.219 | 1.344 | 0.361 | 0.000 |
| 6.2222 | 0.219 | 1.363 | 0.372 | 0.000 |
| 6.3111 | 0.219 | 1.383 | 0.383 | 0.000 |
| 6.4000 | 0.219 | 1.402 | 0.394 | 0.000 |
| 6.4889 | 0.219 | 1.422 | 0.405 | 0.000 |
| 6.5778 | 0.219 | 1.441 | 0.416 | 0.000 |
| 6.6667 | 0.219 | 1.461 | 0.427 | 0.000 |
| 6.7556 | 0.219 | 1.480 | 0.439 | 0.000 |
| 6.8444 | 0.219 | 1.500 | 0.450 | 0.000 |
| 6.9333 | 0.219 | 1.519 | 0.462 | 0.000 |
| 7.0222 | 0.219 | 1.539 | 0.524 | 0.000 |
| 7.1111 | 0.219 | 1.558 | 1.060 | 0.000 |
| 7.2000 | 0.219 | 1.578 | 1.877 | 0.000 |
| 7.2889 | 0.219 | 1.597 | 2.848 | 0.000 |
| 7.3778 | 0.219 | 1.617 | 3.861 | 0.000 |
| 7.4667 | 0.219 | 1.636 | 4.802 | 0.000 |
| 7.5556 | 0.219 | 1.656 | 5.574 | 0.000 |
| 7.6444 | 0.219 | 1.675 | 6.127 | 0.000 |
| 7.7333 | 0.219 | 1.695 | 6.492 | 0.000 |
| 7.8222 | 0.219 | 1.714 | 6.905 | 0.000 |
| 7.9111 | 0.219 | 1.734 | 7.244 | 0.000 |
| 8.0000 | 0.219 | 1.753 | 7.567 | 0.000 |
| 8.0889 | 0.219 | 1.773 | 7.876 | 0.000 |
| 8.1778 | 0.000 | 0.000 | 8.173 | 0.000 |

# Analysis Results

## POC 1



+ Predeveloped    x Mitigated

### Predeveloped Landuse Totals for POC #1

Total Pervious Area: 4.9  
 Total Impervious Area: 0

### Mitigated Landuse Totals for POC #1

Total Pervious Area: 2.46  
 Total Impervious Area: 2.44

Flow Frequency Method: Log Pearson Type III 17B

### Flow Frequency Return Periods for Predeveloped. POC #1

| Return Period | Flow(cfs) |
|---------------|-----------|
| 2 year        | 0.181134  |
| 5 year        | 0.289661  |
| 10 year       | 0.376018  |
| 25 year       | 0.502639  |
| 50 year       | 0.610345  |
| 100 year      | 0.730094  |

### Flow Frequency Return Periods for Mitigated. POC #1

| Return Period | Flow(cfs) |
|---------------|-----------|
| 2 year        | 0.100478  |
| 5 year        | 0.14358   |
| 10 year       | 0.178531  |
| 25 year       | 0.230866  |
| 50 year       | 0.276404  |
| 100 year      | 0.328106  |

### Annual Peaks

#### Annual Peaks for Predeveloped and Mitigated. POC #1

| Year | Predeveloped | Mitigated |
|------|--------------|-----------|
| 1949 | 0.202        | 0.083     |
| 1950 | 0.205        | 0.097     |
| 1951 | 0.173        | 0.081     |
| 1952 | 0.141        | 0.076     |
| 1953 | 0.114        | 0.075     |
| 1954 | 0.717        | 0.093     |
| 1955 | 0.217        | 0.128     |
| 1956 | 0.190        | 0.153     |
| 1957 | 0.263        | 0.129     |
| 1958 | 0.229        | 0.086     |

|      |       |       |
|------|-------|-------|
| 1959 | 0.179 | 0.096 |
| 1960 | 0.173 | 0.106 |
| 1961 | 0.359 | 0.123 |
| 1962 | 0.174 | 0.081 |
| 1963 | 0.293 | 0.080 |
| 1964 | 0.231 | 0.071 |
| 1965 | 0.143 | 0.103 |
| 1966 | 0.084 | 0.079 |
| 1967 | 0.170 | 0.082 |
| 1968 | 0.207 | 0.117 |
| 1969 | 0.671 | 0.085 |
| 1970 | 0.118 | 0.080 |
| 1971 | 0.223 | 0.148 |
| 1972 | 0.138 | 0.092 |
| 1973 | 0.136 | 0.090 |
| 1974 | 0.366 | 0.091 |
| 1975 | 0.140 | 0.075 |
| 1976 | 0.147 | 0.091 |
| 1977 | 0.106 | 0.080 |
| 1978 | 0.124 | 0.075 |
| 1979 | 0.410 | 0.086 |
| 1980 | 0.192 | 0.074 |
| 1981 | 0.121 | 0.078 |
| 1982 | 0.157 | 0.128 |
| 1983 | 0.333 | 0.080 |
| 1984 | 0.162 | 0.188 |
| 1985 | 0.216 | 0.131 |
| 1986 | 0.485 | 0.318 |
| 1987 | 0.219 | 0.232 |
| 1988 | 0.113 | 0.125 |
| 1989 | 0.146 | 0.071 |
| 1990 | 0.153 | 0.122 |
| 1991 | 0.158 | 0.102 |
| 1992 | 0.120 | 0.109 |
| 1993 | 0.115 | 0.071 |
| 1994 | 0.110 | 0.098 |
| 1995 | 0.161 | 0.147 |
| 1996 | 0.303 | 0.136 |
| 1997 | 0.601 | 0.493 |
| 1998 | 0.100 | 0.077 |
| 1999 | 0.131 | 0.103 |
| 2000 | 0.114 | 0.157 |
| 2001 | 0.039 | 0.062 |
| 2002 | 0.149 | 0.104 |
| 2003 | 0.117 | 0.093 |
| 2004 | 0.197 | 0.148 |
| 2005 | 0.137 | 0.093 |
| 2006 | 0.473 | 0.125 |
| 2007 | 0.349 | 0.104 |
| 2008 | 0.405 | 0.315 |
| 2009 | 0.123 | 0.094 |

### Ranked Annual Peaks

Ranked Annual Peaks for Predeveloped and Mitigated. POC #1

| Rank | Predeveloped | Mitigated |
|------|--------------|-----------|
| 1    | 0.7166       | 0.4927    |
| 2    | 0.6705       | 0.3177    |
| 3    | 0.6010       | 0.3147    |

|    |        |        |
|----|--------|--------|
| 4  | 0.4847 | 0.2317 |
| 5  | 0.4728 | 0.1880 |
| 6  | 0.4104 | 0.1569 |
| 7  | 0.4055 | 0.1527 |
| 8  | 0.3665 | 0.1482 |
| 9  | 0.3593 | 0.1477 |
| 10 | 0.3492 | 0.1470 |
| 11 | 0.3327 | 0.1363 |
| 12 | 0.3029 | 0.1315 |
| 13 | 0.2933 | 0.1294 |
| 14 | 0.2630 | 0.1281 |
| 15 | 0.2311 | 0.1277 |
| 16 | 0.2287 | 0.1249 |
| 17 | 0.2230 | 0.1247 |
| 18 | 0.2192 | 0.1226 |
| 19 | 0.2171 | 0.1216 |
| 20 | 0.2158 | 0.1167 |
| 21 | 0.2072 | 0.1091 |
| 22 | 0.2047 | 0.1064 |
| 23 | 0.2015 | 0.1039 |
| 24 | 0.1968 | 0.1037 |
| 25 | 0.1922 | 0.1031 |
| 26 | 0.1897 | 0.1026 |
| 27 | 0.1786 | 0.1019 |
| 28 | 0.1739 | 0.0985 |
| 29 | 0.1732 | 0.0968 |
| 30 | 0.1731 | 0.0964 |
| 31 | 0.1699 | 0.0937 |
| 32 | 0.1617 | 0.0931 |
| 33 | 0.1607 | 0.0929 |
| 34 | 0.1580 | 0.0927 |
| 35 | 0.1568 | 0.0922 |
| 36 | 0.1534 | 0.0912 |
| 37 | 0.1494 | 0.0909 |
| 38 | 0.1472 | 0.0902 |
| 39 | 0.1459 | 0.0865 |
| 40 | 0.1429 | 0.0861 |
| 41 | 0.1409 | 0.0850 |
| 42 | 0.1401 | 0.0825 |
| 43 | 0.1377 | 0.0816 |
| 44 | 0.1371 | 0.0811 |
| 45 | 0.1356 | 0.0806 |
| 46 | 0.1310 | 0.0805 |
| 47 | 0.1238 | 0.0805 |
| 48 | 0.1235 | 0.0800 |
| 49 | 0.1209 | 0.0796 |
| 50 | 0.1204 | 0.0790 |
| 51 | 0.1183 | 0.0778 |
| 52 | 0.1171 | 0.0772 |
| 53 | 0.1152 | 0.0759 |
| 54 | 0.1143 | 0.0754 |
| 55 | 0.1139 | 0.0749 |
| 56 | 0.1135 | 0.0749 |
| 57 | 0.1096 | 0.0736 |
| 58 | 0.1062 | 0.0713 |
| 59 | 0.1004 | 0.0709 |
| 60 | 0.0839 | 0.0707 |
| 61 | 0.0395 | 0.0620 |



Duration Flows  
The Facility PASSED

| Flow(cfs) | Predev | Mit   | Percentage | Pass/Fail |
|-----------|--------|-------|------------|-----------|
| 0.0906    | 15071  | 14245 | 94         | Pass      |
| 0.0958    | 12696  | 9597  | 75         | Pass      |
| 0.1011    | 10243  | 7358  | 71         | Pass      |
| 0.1063    | 8626   | 6021  | 69         | Pass      |
| 0.1116    | 7281   | 5084  | 69         | Pass      |
| 0.1168    | 6130   | 4145  | 67         | Pass      |
| 0.1221    | 5020   | 3187  | 63         | Pass      |
| 0.1273    | 4297   | 2509  | 58         | Pass      |
| 0.1326    | 3670   | 2016  | 54         | Pass      |
| 0.1378    | 3140   | 1636  | 52         | Pass      |
| 0.1431    | 2635   | 1352  | 51         | Pass      |
| 0.1483    | 2274   | 1110  | 48         | Pass      |
| 0.1536    | 1951   | 981   | 50         | Pass      |
| 0.1588    | 1677   | 894   | 53         | Pass      |
| 0.1641    | 1468   | 849   | 57         | Pass      |
| 0.1693    | 1311   | 833   | 63         | Pass      |
| 0.1746    | 1187   | 816   | 68         | Pass      |
| 0.1798    | 1091   | 800   | 73         | Pass      |
| 0.1851    | 1001   | 778   | 77         | Pass      |
| 0.1903    | 922    | 724   | 78         | Pass      |
| 0.1956    | 848    | 696   | 82         | Pass      |
| 0.2008    | 786    | 670   | 85         | Pass      |
| 0.2061    | 718    | 636   | 88         | Pass      |
| 0.2113    | 674    | 608   | 90         | Pass      |
| 0.2166    | 637    | 583   | 91         | Pass      |
| 0.2218    | 614    | 557   | 90         | Pass      |
| 0.2271    | 583    | 527   | 90         | Pass      |
| 0.2323    | 552    | 486   | 88         | Pass      |
| 0.2376    | 522    | 469   | 89         | Pass      |
| 0.2428    | 501    | 453   | 90         | Pass      |
| 0.2481    | 480    | 423   | 88         | Pass      |
| 0.2533    | 456    | 395   | 86         | Pass      |
| 0.2586    | 437    | 378   | 86         | Pass      |
| 0.2638    | 419    | 362   | 86         | Pass      |
| 0.2691    | 396    | 341   | 86         | Pass      |
| 0.2743    | 382    | 326   | 85         | Pass      |
| 0.2796    | 364    | 312   | 85         | Pass      |
| 0.2848    | 350    | 297   | 84         | Pass      |
| 0.2901    | 336    | 280   | 83         | Pass      |
| 0.2953    | 324    | 258   | 79         | Pass      |
| 0.3006    | 316    | 244   | 77         | Pass      |
| 0.3058    | 300    | 229   | 76         | Pass      |
| 0.3111    | 288    | 188   | 65         | Pass      |
| 0.3163    | 277    | 158   | 57         | Pass      |
| 0.3216    | 265    | 145   | 54         | Pass      |
| 0.3268    | 246    | 132   | 53         | Pass      |
| 0.3321    | 235    | 128   | 54         | Pass      |
| 0.3373    | 222    | 126   | 56         | Pass      |
| 0.3426    | 210    | 122   | 58         | Pass      |
| 0.3478    | 198    | 119   | 60         | Pass      |
| 0.3531    | 187    | 116   | 62         | Pass      |
| 0.3583    | 175    | 112   | 64         | Pass      |
| 0.3636    | 164    | 101   | 61         | Pass      |

|        |     |    |     |      |
|--------|-----|----|-----|------|
| 0.3688 | 154 | 90 | 58  | Pass |
| 0.3741 | 146 | 79 | 54  | Pass |
| 0.3793 | 135 | 75 | 55  | Pass |
| 0.3846 | 126 | 71 | 56  | Pass |
| 0.3898 | 114 | 69 | 60  | Pass |
| 0.3951 | 94  | 65 | 69  | Pass |
| 0.4003 | 80  | 61 | 76  | Pass |
| 0.4056 | 68  | 57 | 83  | Pass |
| 0.4108 | 62  | 54 | 87  | Pass |
| 0.4161 | 55  | 50 | 90  | Pass |
| 0.4213 | 46  | 47 | 102 | Pass |
| 0.4266 | 41  | 44 | 107 | Pass |
| 0.4318 | 40  | 39 | 97  | Pass |
| 0.4371 | 37  | 34 | 91  | Pass |
| 0.4423 | 32  | 27 | 84  | Pass |
| 0.4476 | 30  | 24 | 80  | Pass |
| 0.4528 | 22  | 21 | 95  | Pass |
| 0.4581 | 18  | 17 | 94  | Pass |
| 0.4633 | 14  | 8  | 57  | Pass |
| 0.4686 | 8   | 7  | 87  | Pass |
| 0.4738 | 7   | 6  | 85  | Pass |
| 0.4791 | 5   | 5  | 100 | Pass |
| 0.4843 | 5   | 4  | 80  | Pass |
| 0.4896 | 4   | 2  | 50  | Pass |
| 0.4948 | 4   | 0  | 0   | Pass |
| 0.5001 | 4   | 0  | 0   | Pass |
| 0.5053 | 4   | 0  | 0   | Pass |
| 0.5106 | 4   | 0  | 0   | Pass |
| 0.5158 | 4   | 0  | 0   | Pass |
| 0.5211 | 4   | 0  | 0   | Pass |
| 0.5263 | 3   | 0  | 0   | Pass |
| 0.5316 | 3   | 0  | 0   | Pass |
| 0.5368 | 3   | 0  | 0   | Pass |
| 0.5421 | 3   | 0  | 0   | Pass |
| 0.5473 | 3   | 0  | 0   | Pass |
| 0.5526 | 3   | 0  | 0   | Pass |
| 0.5578 | 3   | 0  | 0   | Pass |
| 0.5631 | 3   | 0  | 0   | Pass |
| 0.5683 | 3   | 0  | 0   | Pass |
| 0.5736 | 3   | 0  | 0   | Pass |
| 0.5788 | 3   | 0  | 0   | Pass |
| 0.5841 | 3   | 0  | 0   | Pass |
| 0.5893 | 3   | 0  | 0   | Pass |
| 0.5946 | 3   | 0  | 0   | Pass |
| 0.5998 | 3   | 0  | 0   | Pass |
| 0.6051 | 2   | 0  | 0   | Pass |
| 0.6103 | 2   | 0  | 0   | Pass |

## Water Quality

### Water Quality BMP Flow and Volume for POC #1

|                                |             |
|--------------------------------|-------------|
| On-line facility volume:       | 0 acre-feet |
| On-line facility target flow:  | 0 cfs.      |
| Adjusted for 15 min:           | 0 cfs.      |
| Off-line facility target flow: | 0 cfs.      |
| Adjusted for 15 min:           | 0 cfs.      |

# LID Report

| LID Technique  | Used for Treatment?      | Total Volume Needs Treatment (ac-ft) | Volume Through Facility (ac-ft) | Infiltration Volume (ac-ft) | Cumulative Volume Infiltration Credit | Percent Volume Infiltrated | Water Quality | Percent Water Quality Treated | Comment                           |
|--|--------------------------|--------------------------------------|---------------------------------|-----------------------------|---------------------------------------|----------------------------|---------------|-------------------------------|-----------------------------------|
| Vault 1 FOC  | <input type="checkbox"/> | 673.82                               |                                 |                             | <input type="checkbox"/>              | 0.00                       |               |                               |                                   |
| Total Volume Infiltrated                               |                          | 673.82                               | 0.00                            | 0.00                        |                                       | 0.00                       | 0.00          | 0%                            | No Treat. Credit                  |
| Compliance with LID Standard 8% of 2-yr to 50% of 2-yr |                          |                                      |                                 |                             |                                       |                            |               |                               | Duration Analysis Result = Passed |

## *Model Default Modifications*

Total of 0 changes have been made.


### *PERLND Changes*

No PERLND changes have been made.


### *IMPLND Changes*

No IMPLND changes have been made.

Appendix  
Predeveloped Schematic



Mitigated Schematic



**APPENDIX B**

**MAINTENANCE & OPERATIONS MANUAL  
(with construction submittal)**

**APPENDIX C**  
**GEOTECHNICAL REPORT**  
**(with construction submittal)**