


N 6"PIPE

RAW 17-0807 8/7/17

1" = 30'



CESCL NOTES:

- 1. PROJECTS THAT DISTURB ONE OR MORE ACRES MUST HAVE SITE INSPECTIONS CONDUCTED BY A CERTIFIED EROSION AND SEDIMENT CONTROL LEAD (CESCL). BY THE INITIATION OF CONSTRUCTION, THE SWPPP MUST IDENTIFY THE CESCL OR INSPECTOR, WHO MUST BE PRESENT ON-SITE OR ON-CALL AT ALL TIMES.
- 2. THE CESCL OR INSPECTOR MUST HAVE THE SKILLS TO ASSESS THE: • SITE CONDITIONS AND CONSTRUCTION ACTIVITIES THAT COULD
- IMPACT THE QUALITY OF STORMWATER. • EFFECTIVENESS OF EROSION AND SEDIMENT CONTROL MEASURES
- USED TO CONTROL THE QUALITY OF STORMWATER DISCHARGES.
- 3. THE CESCL OR INSPECTOR MUST EXAMINE STORMWATER VISUALLY FOR THE PRESENCE OF SUSPENDED SEDIMENT, TURBIDITY, DISCOLORATION, AND OIL SHEEN. THEY MUST EVALUATE THE EFFECTIVENESS OF BMPS AND DETERMINE IF IT IS NECESSARY TO INSTALL, MAINTAIN, OR REPAIR BMPS TO IMPROVE THE QUALITY OF STORMWATER DISCHARGES.
- 4. BASED ON THE RESULTS OF THE INSPECTION, CONSTRUCTION SITE OPERATORS MUST CORRECT THE PROBLEMS IDENTIFIED BY:
- REVIEWING THE SWPPP FOR COMPLIANCE WITH THE 13 CONSTRUCTION SWPPP ELEMENTS AND MAKING APPROPRIATE REVISIONS WITHIN 7 DAYS OF THE INSPECTION.
- IMMEDIATELY BEGINNING THE PROCESS OF FULLY IMPLEMENTING AND MAINTAINING APPROPRIATE SOURCE CONTROL AND/OR TREATMENT BMPS AS SOON AS POSSIBLE, ADDRESSING THE PROBLEMS NOT LATER THAN WITHIN 10 DAYS OF THE INSPECTION. IF INSTALLATION OF NECESSARY TREATMENT BMPS IS NOT FEASIBLE WITHIN 10 DAYS, THE CONSTRUCTION SITE OPERATOR MAY REQUEST AN EXTENSION WITHIN THE INITIAL 10-DAY RESPONSE PERIOD.
- DOCUMENTING BMP IMPLEMENTATION AND MAINTENANCE IN THE SITE LOG BOOK (SITES LARGER THAN 1 ACRE).
- THE CESCL OR INSPECTOR MUST INSPECT ALL AREAS DISTURBED BY CONSTRUCTION ACTIVITIES, ALL BMPS, AND ALL STORMWATER DISCHARGE POINTS AT LEAST ONCE EVERY CALENDAR WEEK AND WITHIN 24 HOURS OF ANY DISCHARGE FROM THE SITE. (FOR PURPOSES OF THIS CONDITION, INDIVIDUAL DISCHARGE EVENTS THAT LAST MORE THAN ONE DAY DO NOT REQUIRE DAILY INSPECTIONS. FOR EXAMPLE, IF A STORMWATER POND DISCHARGES CONTINUOUSLY OVER THE COURSE OF A WEEK, ONLY ONE INSPECTION IS REQUIRED THAT WEEK.) THE CESCL OR INSPECTOR MAY REDUCE THE INSPECTION FREQUENCY FOR TEMPORARY STABILIZED, INACTIVE SITES TO ONCE EVERY CALENDAR MONTH.

CONSTRUCTION SEQUENCE:

- * CONTACT CITY OF MONROE, 360.794.7400 AND SCHEDULE PRECONSTRUCTION MEETING.
- 1. CLEARING/CONSTRUCTION LIMITS SHALL BE STAKED & SILT FENCING INSTALLED.
- 2. CONSTRUCT CONSTRUCTION ENTRANCE.
- 3. CLEAR, GRUB AND REMOVE ALL VEGETATION WITHIN THE CLEARING LIMITS.
- 4. CONSTRUCT DETENTION VAULT/SEDIMENT PONDS WITH OUTFALLS.
- 5. ROUGH GRADE SITE WITH INTERCEPTOR SWALE DITCHES AS SHOWN ON THE EROSION CONTROL PLAN. ALL TEMPORARY AND PERMANENT EROSION CONTROL MEASURES SHALL BE MAINTAINED. AND REPAIRED AS NEEDED TO ASSURE CONTINUED PERFORMANCE.
- 6. INSTALL STORM WATER COLLECTION SYSTEM W/ SEDIMENT PROTECTION MEASURES.
- 7. INSTALL SEWER AND WATER UTILITIES AND SERVICES.
- 8. FINAL GRADE PAVEMENT AREA AND INSTALL GRAVEL BASE OR ATB.
- 9. CONSTRUCT CURB, SIDEWALK, DRIVEWAYS AND PARKING PER PLAN. OBTAIN RIGHT-OF-WAY DISTURBANCE PERMIT PRIOR TO WORK WITHIN R.O.W.
- CONSTRUCT/COORDINATE POWER, GAS, TELEPHONE, CABLE SERVICES PER THE RESPECTIVE COMPANIES STANDARDS AND RELOCATION OF POWER
- 11.COMPLETE IRRIGATION AND LANDSCAPING.
- INSTALL PAVEMENT.
- CLEAN STORM DRAINAGE CONVEYANCE SYSTEM (DO NOT FLUSH), AFTER VEGETATION HAS BEEN ESTABLISHED.
- 14. WHEN SITE IS STABLE, REMOVE REMAINING TEMPORARY ESC FACILITIES.

TESC NOTES:

- 1. ALL TESC MEASURES MUST COMPLY WITH THE MONROE STANDARDS AND SPECIFICATIONS AND THE DEPARTMENT OF ECOLOGY 2005 STORMWATER MANUAL FOR THE PUGET SOUND BASIN.
- 2. THE TESC SYSTEM SHALL BE INSTALLED AND INSPECTED BY THE PUBLIC WORKS INSPECTOR PRIOR TO ALL OTHER CONSTRUCTION.
- 3. AS CONSTRUCTION PROGRESSES AND SEASONAL CONDITIONS DICTATE, THE EROSION CONTROL FACILITIES SHALL BE MAINTAINED AND/OR ALTERED AS REQUIRED BY THE CITY ENGINEER TO ENSURE CONTINUING EROSION/SEDIMENT CONTROL.
- 4. THE PUBLIC RIGHT-OF-WAY SHALL BE KEPT CLEAN. TRACKING OF MUD AND DEBRIS FROM THE SITE WILL NOT BE ALLOWED. FAILURE TO COMPLY WITH THIS CONDITION WILL RESULT IN A STOP WORK ORDER PER MONROE MUNICIPAL CODE CHAPTER 12.32, CLEAN CONDITIONS OF PUBLIC RIGHT-OF-WAY.

CALL 48 HOURS BEFORE YOU DIG 811



GRADING QUANTITIES: CUT = 300 C.Y.FILL = 900 C.Y.

— X — X — SILT FENCE

LIMITS OF CLEARING

INTERCEPTOR SWALE


ROCK CHECK DAM

CB INLET PROTECTION

GRADING QUANTITIES CALCULATED USING AUTOCAD GRID SUBTRACTION METHOD COMPARING EXISTING GRADE TO FINISHED GRADE.

FILE NO.:

DESCRIPTION							,
DATE							
R#	\bigvee	∇	\bigvee	\bigvee	\bigvee	∇	∇






 \Box

17-0807 8/7/17 1" = 30'

MAIN BROOK TOWNHOMES

SECTION 1, TOWNSHIP 21N, RANGE 6E, W.M.




SOCK TYPE INLET FILTER SPECS:
DRAINGUARD — OIL AND SEDIMENT MODEL
DIMENSIONS: 48" x 36" x 18"HIGH
WEIGHT (DRY): 1 LBS
SEDIMENT CAPACITY: 40 LBS FILTER: 500 GPM BYPASS: 700 GPM

INSTALLATION INSTRUCTIONS:
1. REMOVE GRATE. 2. PLACE DRAINGUARD IN CB.
3. REPLACE GRATE.
4. TRIM EXCESS FABRIC


REMOVAL INSTRUCTIONS: 1. SECURE PULL STRAP AND REMOVE GRATE. 2. REMOVE INSERT 3. DISPOSE OF INSERT OR CLEAN AND REUSE.

NOTE: EQUIVALENT PRODUCT SHALL AT A MINIMUM HAVE A TREATMENT FLOW RATE OF 225 GPM.

INLET PROTECTION (PAVED AREAS) NOT TO SCALE



GRAVEL CONSTRUCTION ENTRANCE










1" = 30'

FILE NO.:











MAIN BROOK TOWNHOMES

SECTION 1, TOWNSHIP 21N, RANGE 6E, W.M.












FILE NO.:





MAIN BROOK TOWNHOMES


SECTION 1, TOWNSHIP 21N, RANGE 6E, W.M.












FILE NO.:




- :900 PVC PIPE THERE SHALL BE A MINIMUM OF 3 FEET BETWEEN TAPS AND STAGGER T ILL OTHER PIPES MATERIALS THERE SHALL BE A MINIMUM OF 2 FEET BETWEEN TAPS.
- MUELLER C110 COMPRESSION FITTING. FEMALE IRON PIPE THREAD BY FEMALE COPPER TUBE SIZE.
- (D) 1 INCH (MINIMUM) COPPER TUBE SIZE HIGH DENSITY WEIGHT POLYETHYLENE (200 PSI) OR 1 INCH COPPER TUBING TYPE K. SAND BEDDING FOR SERVICE LINE IS REQUIRED.
- (F) METER BOXES IN NON TRAFFIC AREAS SHALL BE CARSON METER BOX #1220113 OR APPROVED EQUAL. METER BOXES IN TRAFFIC AREAS SHALL BE OLD CASTLE 1527 WITH SOLID DUCTILE IRON LIDS OR APPROVED EQUAL.


SEWER NOTES:

- 10 GAUGE INSULATED LOCATOR WIRE. USE WIRE NUT (OR EQUAL) TO CONNECT TO MAIN LINE WIRE.
- PRON PIPE SIZE HIGH DENSITY WEIGHT POLYETHYLENE (200 PSI) OR 1* COPPER PIPE TYPE K. FOR NEW CONSTRUCTION EXTEND TEN FEET INTO PROPERTY. CUSTOMER SIDE SHALL BE BRASS TO POLY (OR COPPER) CONNECTION. (J) 3/4" FEMALE IPS BRASS COUPLER TO 3/4" MALE 1PS X 1" C110 COMPRESSION FITTING. NO TWO PIECE UNIONS ALLOWED ON CITY SIDE, UNIONS ALLOWED ON CUSTOMER TAIL SIDE ONLY.

1	DESIGNATIO			
	3/4" X 5/8" 8	' X 5/8" & 1" WATER SERVICE		
SCALE		REVISED		
	NOT TO SCALE	JAN 11, 2016		



FIRE HYDRANT ASSEMBLY



WATER NOTES:

1. ALL WORK AND MATERIALS SHALL CONFORM TO THE CITY OF MONROE STANDARDS AND SPECIFICATIONS.

2. NO PART OF THE SANITARY SEWER SYSTEM SHALL BE COVERED, CONCEALED OR PUT INTO USE UNTIL IT HAS BEEN TESTED, INSPECTED AND APPROVED BY THE CITY INSPECTOR.

3. APPROXIMATE LOCATIONS OF EXISTING UTILITIES HAVE BEEN OBTAINED FROM AVAILABLE RECORDS AND ARE SHOWN FOR CONVENIENCE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFICATIONS OF LOCATIONS AND TO AVOID DAMAGE TO ANY ADDITIONAL UTILITIES NOT SHOWN. IF CONFLICTS WITH EXISTING UTILITIES ARISE DURING CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE PUBLIC WORKS INSPECTOR AND ANY CHANGES REQUIRED SHALL BE APPROVED BY THE CITY ENGINEER PRIOR TO COMMENCEMENT OF RELATED CONSTRUCTION ON THE PROJECT.

4. ALL SEWER MAIN EXTENSIONS WITHIN THE PUBLIC RIGHT-OF-WAY OR IN EASEMENTS MUST BE STAKED BY SURVEY FOR LINE AND GRADE PRIOR TO STARTING CONSTRUCTION.

5. SIDE SEWERS SHALL BE TESTED AT THE SAME TIME THE MAIN IS TESTED. PRESSURE TESTS SHALL BE AT 4.5 P.S.I. FOR 15 MIN.

6. VIDEO REPORT REQUIREMENTS: TELEVISION INSPECTION IS REQUIRED ON ALL NEW SEWER MAINS. DEFICIENCIES NOTED BY THE TV CAMERA INSPECTION MUST BE CORRECTED TO THE SATISFACTION OF THE CITY ENGINEER.

7. MARK ENDS OF SIDE SEWER STUBS W/ GREEN 2X4 LABELED "SEWER" AS PER LATEST SEWER SERVICE DETAIL.

1. FOR ALL DESIGN, CONSTRUCTION AND MATERIALS SPECIFICATIONS REFER TO THE CITY OF MONROE PUBLIC WORKS DESIGN AND CONSTRUCTION

2. THE WATER MAIN SHALL BE INSTALLED ONLY AFTER THE ROADWAY SUBGRADE IS BACKFILLED, GRADED AND COMPACTED IN CUT AND FILL AREAS. THE ROAD CENTERLINE SHALL BE STAKED ALONG WITH THE PROPERTY CORNERS.

3. IF THE INITIAL TAP OR EXTENSION REQUIRES SHUTTING DOWN AN EXISTING WATER MAIN, THE CITY MAY REQUIRE TWO WEEKS NOTIFICATION IN ORDER TO PLACE A PUBLIC NOTICE IN THE LOCAL PAPER. NO TAPS WILL BE ALLOWED ON FRIDAY, OR WEEKENDS. THE MONROE UTILITIES DEPARTMENT SHALL OPERATE ALL WATER VALVES IN RIGHT-OF-WAY.

4. ALL FITTINGS AND MATERIALS REMOVED FROM EXISTING MAINS SHALL BE RETURNED TO THE UTILITIES DEPARTMENT.

5. THE CONTRACTOR SHALL NOTIFY VESTED OWNERS OF EXISTING EASEMENTS IN WRITING 10 DAYS PRIOR TO STARTING WORK. THE PROPERTY OWNER PRIOR TO CITY ACCEPTANCE MUST SIGN A LETTER OF SATISFACTION OF RESTORATION OF EXISTING EASEMENT.

6. THE MONROE FIRE DEPARTMENT MUST APPROVE ALL ON-SITE FIRE PROTECTION IMPROVEMENTS. THE MONROE FIRE DEPARTMENT PRIOR TO INSTALLATION MUST APPROVE LOCATION OF THE FIRE DEPARTMENT CONNECTION.

7. NO CONNECTION TO EXISTING MAIN LINES WILL BE ALLOWED, EXCEPT BY MEANS OF AN APPROVED BACKFLOW PREVENTION DEVICE, PRIOR TO SATISFACTORY FLUSHING, TESTING, DISINFECTION, AND RECEIPT OF SATISFACTORY BACTERIOLOGICAL TESTS.

8. HYDROSTATIC PRESSURE TEST

a. ALL NEW MAINS SHALL BE BLOCKED AND SATISFACTORILY PRESSURE AND PURIT TESTED AND ALL DISINFECTION WATER

PROPERLY DISPOSED OF PRIOR TO CONNECTING TO THE EXISTING MAINS. ALL SERVICES AND METER SETTERS SHALL BE OPEN AT THE CORPORATION STOP AT THE MAIN AND TESTED IN

CONJUNCTION WITH THE MAIN TESTING. AS SOON AS PIPE IS SECURED AGAINST MOVEMENT UNDER PRESSURE, IT MAY BE FILLED WITH WATER. SATISFACTORY

PERFORMANCE OF AIR RELEASE VALVES SHOULD BE CHECKED WHILE THE LINE IS FILLING. AFTER THE PIPE IS FILLED AND ALL AIR EXPELLED, IT SHALL BE PUMPED TO A TEST PRESSURE OF 250 PSI. UP TO A MAXIMUM TEST PRESSURE OF 300 PSI. THE PRESSURE SHALL BE MAINTAINED FOR A PERIOD OF 1 HOUR, WITH NO LOSS.

CALL 48 HOURS BEFORE YOU DIG 811

RAW 17-0807 8/7/17

N.T.S.

